



The Switch to Prime is On.

Client:

Diamond Offshore

Project Name:

Ocean Quest

Location:

Port Arthur, TX

Completion:

December 2007

Governing Bodies:

ABS, USCG, IEEE, NEC, MMS



Services Provided:

- Rerouted and replaced power cabling for Top Drive from underneath rig to a more readily accessible location going around the moon pool area on the main deck.
- Rerouted and replaced power cabling for three (3) Mud Pumps from underneath rig to a more readily accessible location going around the moon pool on the main deck.
- Rerouted and replaced power cabling for Anchor Winches 3, 4, 5, and 6 from underneath rig to a more readily accessible location going around the moon pool area on the main deck.
- Rerouted and replaced power cabling for MCC #3, MCC #4, and the emergency MCC from underneath rig to a more readily accessible location going around the moon pool area on the main deck.
- Designed new route for cable tray installation.
- Installed new cable tray along the new route on the main deck for rerouted cabling.
- Installed new S8 transits along new route for installation requirements.

Beaumont Office
(877) 211-7874 or (409) 835-5353
Fax (409) 835-5455
6155 Hwy. 347
Beaumont, TX 77705



www.SwitchToPrime.com

Lafayette Office
(337) 232-2343
Fax (337) 704-0132
2407 South College Rd.
Lafayette, LA, 70508